issue (Potential impact)	Assessment (Sample assessments)	Mitigation Measure	Schedul e/ Duratio n of the Mitigati on Measur es	Instrum ent of implem entatio n (POW, Contrac t, IDP, or O&M Plan)*	Respon sible Unit
Temporary increase in sedimentation during construction		[] Earthmoving/ cutting of slopes to be done during dry months [] Proper disposal and compaction of spoils	During Constru ction	DED/POW; Contract	I- BUILD HEAD and CONT RACT OR
2. Potential contamination of surface and groundwater with oil/grease	[] Waste oil and grease from equipment could contaminate surface water [] There will be no or insignificant amount of waste oil/grease	[] Proper handling and disposal of waste oil and grease	During Constru ction	Contract	J- BUILD HEAD and CONT RACT OR
3. Potential contamination with human waste	[] Construction workers would be temporarily housed in a base camp [] Workers would be mostly locals and are expected to go home to their respective houses after works	[] Set up adequate latrine/toilet facility at the base camp	During Constru ction	Contract	i- BUILD HEAD and CONT RACT OR
4. Potential disruption of traffic flow	[] The access road and/or segments to be rehabilitated need is vital to daily activities of the residents and farmers and need to be kept open to traffic during construction [] The construction will not affect daily movement of residents and farmers	[] Keep the road open to traffic flow and minimize disruptions along the access road and/or construction area; Provide adequate warning signs and traffic personnel when necessary; [] Undertake regular maintenance measures on the passable portions of the roads	During Constru ction	Contract	BUILD HEAD and CONT RACT OR
5. Potential dust/mud nuisance during construction	Roads could become powdery during dry days and muddy during rainy days of the construction period [] Access road and/or the construction/ rehabilitation works passes through a populated area	[] Undertake sprinkling of road (including access roads) during dry days, and filling up of potholes during rainy days, especially in residential areas []Set up speed limits for vehicles, especially within	During Constru ction	Contract	I- BUILD HEAD and CONT RACT OR