E. Preparation of the Environmental Management Plan (EMP)

GUIDE ON HOW TO USE THE TEMPLATE FOR PROJECT DESCRIPTION/

	ENVIRONMENTAL MANAGEMENT PLAN (PD/EMP) FOR FARM-TO-MARKET (FMR) ROADS
A.	GENERAL GUIDANCE
1.	This PD/EMP Template is applicable only for farm-to-market roads with the following project limits which are not required to secure an Environmental Compliance Certificate (ECC), pursuant to DAO 03-30: • For new construction: Less than 2 kms • For rehabilitation/improvement: <50% increase in capacity (in terms of length/ width)
2.	This PD/EMP Template is designed and intended to be used primarily for the following
	 purposes: Selection of the most environmentally and socio-culturally acceptable FMR location and design; and Identification of the requirement of other relevant Philippine regulations, and the environmental and social safeguard requirements of Financing Institutions (FIs) (for proposals which passed the loan-eligibility screening of the FI).
3.	This PD/EMP Template may also be used to secure a Certificate on Non-Coverage (CNC)
3.	from the DENR-EMB/LLDA/DENR-ARMM. However, the CNC is <u>NOT</u> a government requirement, thus, application for a CNC is at the <u>OPTION/REQUEST</u> of the Proponent for whatever purpose it may serve.
B.	GUIDANCE ON SPECIFIC SECTIONS
4.	PROJECT a) Project Name: REHABILITATION OF TAYUGO-PALADONG FMR. D
5.	PROPO- Project I.D. No. R.I-01-ISU-SKP-12
	NENT ID Municipal Government of Isulan, Sultan Kudarat, represented by the Hon.
	SECTION Diosdado G. Pallasigue, 064-201-3526/064-201-3424
6.	PROJECT Project Length = 1.809 Kilometers
0.	DESIGN Direct Road Influence Area = 683 hectares,
	& Project Beneficiaries = 826 population, male = 405, Female = 421 with
	SPECIFI- Number of HHs = 531
	CATIONS Total Project Cost: P5,056,607.02
	SECTION World Bank Loan Proceeds: P4,045,285.62 or 80% of Project Cost
	LGU Equity: P505,660.70 or 10% of Project Cost

		GOP Equity: P505,660.70 or 10% of Project Cost					
7.	COMMIT	The LGU committed to allocate the counterpart of the projects on its 20%					
	-MENT	Development Fund. At the same time Barangay Government committed also					
	SECTION	their share in their 20% Development Fund for the monitoring and maintenance					
		of the project.					
8.	ENVIRO	Check the relevant impacts, mitigating measures* and monitoring parameters*					
	N-	per project phase: Pre-construction, Construction and Operation & Maintenance					
	MENTAL	Phases. Check the appropriate responsible unit and identify the specific lead					
	MANAG	entity. Provide a project-specific estimate of the mitigation and monitoring					
	E-MENT	cost. Assumptions & calculations may be attached, particularly for social					
	&	measures.					
	MONITO						
	R-ING	*The measures and monitoring parameters are intended to be implemented by					
	PLAN	the Proponent under its self-regulation program. For FI-assisted projects, the					
	SECTION	same may be used by the Project Management Office (PMO) or implementing					
		Government Agency (GA) for the monitoring & evaluation (M&E) of the					
		Proponent's performance. The PD/EMP M&E shall be consolidated with the					
		Project M&E for an integrated evaluation of performance & not incur additional					
		costs.					
9.	SIGNAT	Proponent checks either of the "Yes" or "No" box if it has a) reevaluated					
	O-RY	Project Design vis-a-vis the PD/EMP results, & b) has actually integrated of the					
	SECTION	Mitigating/Monitoring Costs in the Final Project Cost. If "Yes" to both					
		questions, the Proponent staff who prepared the PD/EMP signs off the					
		appropriate space, followed by the endorsement signature of the Proponent's					
		authorized representative. For loan applications, the PD/EMP is submitted with					
		the loan package to the PMO/GA* for review/approval.					
		*The PMO or GA Reviewer and Approving Authority consecutively sign-off					
		the space provided in the revised & final version of the PD/EMP Template.					

PD/EMP Template	:	
No./Ver		
Project Type	••	FARM-TO-MARKET ROADS
DAO 03-30 Non-	:	a) For new construction: Less than 2 kms
Covered Project		b) For rehabilitation/improvement: <50% increase in capacity (in
Limits		terms of length / width)

1.0	Project ID				
1.1	Project Name/Title		Construction / x Rehabilitation of	TAYUGO -	
			PALADONG FMR		
		:		(Name of FMR)	
1.2	Project Cost		P5,056,607.02 % Loan: FI:		
	·	:			
1.3	Project Location				
	-		Barangay Tayugo, Isulan, Sultan Kudara	at, Region XII	
		:	(Sitio/Zone, Barangay, Municipality/City, Province, Region	on)	
Attachment 1: Location/Vicinity map of 1:10,000 scale, indicating the FMR location and showing major landmarks in the					
vicini	ity				
Attac	hment 2: Site photos facing N	V, S, 1	E, W of the site		

2.0	Proponent ID		
2.1	Name of Proponent	:	HON. DIOSDADO G. PALLASIGUE, Municipal Mayor
2.2	Address of		Municipal Government of Isulan, Sultan Kudarat, Region
	Proponent		XII
		:	(Sitio/Zone, Barangay, Municipality/City, Province, Region)
2.3	Contact Person		OVETTE C. VIRAY
			MRDP Focal Person (Rural Infrastructure)
			064-201-3470 / 09065860046 / denvette2000@gmail.com
		:	(State Name, Position, Landline, Cell phone, Fax and/or Email address)

3.0	Project Design & Specifications (Instructions: Check applicable box/es & input specs on						
	space provided. Attach supplemental information where deemed necessary for						
	planning/costing purposes)						
3.1	Length: [] construction: m [x] rehabilitation/improvement: <u>1809</u> meters (% of total FMR						
	length of m)						
3.2	Width: [] construction: m [] rehabilitation/improvement: <u>6</u> meters (% of total FMR width						
	ofm)						
3.3	Road Material: []earth [x]gravel [] asphalt [x] concrete						
3.4	Bank stabilization: []Left Bank:m []Right Bank:m Type:						
	[]vegetative [] mechanical/riprap						
3.5	Drainage Description:						
3.6	Temporary Facilities:						
	[x] Basecamp/admin/canteen/sanitary facilities [] Construct [x] Lease Area: 50 m ²						
	<u> </u>						
	[x] Staging/Motorpool [] Construct [x] Lease Area: <u>50</u> m ²						
	[x] Solid Waste Disposal Facility Area: 50 m ² , locatedm, []N []S						
	[] E [] W of the site						

3.7	Construction Equipment and Ancillary Facilities:								
	[x] Transport vehicles:	_ (quantity)							
	[x] Heavy equipment :	_ (quantity)							
	[x] Generator Set :	_ (quantity); horsepower or kW							
	[] Fuel Tank :	_ (quantity); liters (volume)							

4.0 Commitment Section

We are committed to:

- a) Comply with all mitigating measures necessary to minimize negative impacts & address enhancement measures to maximize positive impacts, as presented in Section 5.0 of the PD/EMP Template below;
- b) Comply with other applicable rules, regulations, guidelines and criteria; and
- c) Properly inform the contractor, residents of the barangay and other stakeholders on the PD/EMP commitments and other public agreements in connection with the project.

5.0 Environmental Management and Monitoring Plan (Instructions: Check applicable box/es &/or input data where asked. Attach supplemental information where deemed necessary for planning/costing purposes)

Project Phase / Activities	Possible Environmental Impacts	Mitigating Measures	Monitoring Parameters	Responsib le Agency/ Unit	Cost of Mitigation/ Monitoring			
1.0 Pre-constru	1.0 Pre-construction Phase (Site Selection, Planning/Design, Procurement, Hiring)							
1.1 Site Selection and Planning/ Design	☐ Encroachment in Protected Areas/ natural/critical habitats (e.g. mangrove/forest ecosystems, coral reefs, & other aquatic ecosystems) ☐ Inconsistent with protected area zoning	 □ Consider alternative site or design to be compatible with the PA zoning □ Secure PAMB Resolution for PA 		□ LGU □ PO/NG O	NONE			
	☐ Damage to flora and disturbance to fauna in forest areas/other critical habitats	 □ Consider alternative site or design to reduce effects on flora and fauna □ Secure Special Land Use Permit, Tree Cutting Permit and/or Right-of-Way Permit from DENR-FMB and permits from PAWB for affected wildlife 		☐ LGU ————————————————————————————————————	NONE			
	✓ Land acquisition, ROW conflict, resettlement, structure and crops damage, business loss	□ Consider alternative site with less or no involuntary resettlement issues ✓ Secure Deed of Donation or Quit Claim on land □ Prepare compensation package, e.g. Land Acquisition, Resettlement & Rehabilitation Plan (LARRP) or Resettlement Action Plan (RAP) thru prior consultation with Project Affected Persons (PAPs) □ Identify resettlement site (if selected as option) and subject the RAP to consultation with host community □ Implement the LARR/RAP, including payments of compensation, at least a month prior to start of Construction Works		□ LGU	P5,000.00			
	☐ Encroachment in areas with IPs/lands with Ancestral Domain Claim	 □ Reroute FMR if possible to lessen impacts, unless the IPs are among the beneficiaries of the FMR □ Apply for FBI and secure FPIC from the IPs thru the NCIP 		☐ LGU ————————————————————————————————————	NONE			
	☐ Damage or cause disturbance to	☐ Change the FMR location or design to avoid or lessen		□ LGU				

Project Phase / Activities	Possible Environmental Impacts	Mitigating Measures	Monitoring Parameters	Responsib le Agency/ Unit	Cost of Mitigation/ Monitoring
	adjacent or nearby sites of Cultural Heritage	probability of damage ☐ Secure NHI clearance & coordinate on design/ construction works		□ PO/NG O	NONE
	✓ Unstable or disturbed slopes/ banks may cause damage to FMR	✓Include in the design appropriate erosion control, slope stabilization and protection measures		□ LGU □ PO/NG O	c/o DED
	Negative reactions from the public due to lack of information and coordination	✓ Hold consultative meetings with project beneficiaries and affected persons on the project components and mgt plan		☐ LGU ————————————————————————————————————	P5,000.00
	✓ Damage existing utilities and structures, resulting in disruption of service	✓ Re-locate or redesign road route to avoid or minimize damage ✓ Conduct prior coordination with utility companies and undertake timely information to the public to minimize inconvenience for loss of service		☐ LGU ————————————————————————————————————	
1.2 Procurement	✓ Possible illegal or unauthorized sourcing of raw/construction materials	✓ Procure construction materials from licensed sources, i.e. for sand and gravel, from those with valid MGB/EMB permits; for timber resources, from those with valid FMB/EMB permits		c/o O & M	
1.3 Hiring of labor and other manpower services	✓Increased employment opportunity and community income ✓Entry of external workforce	✓ Give hiring preference to qualified local community residents, particularly those who will be displaced		c/o Contractor & LGU	
2.0 Construct		<u> </u>			
2.1 Mobilization/ Temfacil /Bridge Construction/ Demob	✓ Soil erosion and landslides due to clearing/ excavation operations	✓ Provide slope protection through bank compaction, rip-rapping on critical sections, or vegetative stabilization ☐ Designate a Spoils Storage Area, with topsoil set aside for later use and allow maximum re-use of spoils	☐ Presence of eroded areas near the site ☐ Occurrence of landslide		c/o D.E.D
	☐ Removal of vegetation and disturbance to wildlife	 □ Secure prior DENR Tree Cutting Permit (TCP) □ Do replacement planting with double purpose of serving as vegetation buffers for disturbed wildlife □ In forest roads, put up wildlife conservation signs, and set guidelines with corresponding IEC for workers to prohibit wildlife collection, hunting, 	☐ Presence of FMB TCP ☐ Area replanted ☐ Presence of signages ☐ # of violations to set guidelines	Contractor:	

Project Phase / Activities	Possible Environmental Impacts	Mitigating Measures	Monitoring Parameters	Responsib le Agency/ Unit	Cost of Mitigation/ Monitoring
		poaching, with meaningful consequences for violation such as employment termination			
	✓ Dust suspension from spoils stockpiles, vehicle movement in unpaved roads & construction works	 ✓ Compact spoils storage areas ✓ Wet areas of dust sources to minimize discomfort to nearby residents ✓ Control of vehicle speed to lessen suspension of road dust 	□# public complaints received by Proponent/ Contractor	Contractor:	
	✓ Obnoxious gas & particulate emissions from vehicles, heavy equipment & genset	✓ Regular equipment M&R ☐ Contractor to present proof of compliance with emission standards as part of the annual vehicle registration process	☐Presence of black smoke from construction sources	Contractor:	
	✓ Noise generation from heavy equipment & genset operations	✓ Schedule equipment movement during non-peak hours of daytime vehicular traffic ✓ Minimize nor preferably no night-time construction activities □ Provide housing for gensets, if near residences ✓ Provide silencers/mufflers for heavy equipment	□# public complaints received by Proponent/ Contractor	Contractor:	
	✓Increased river turbidity & siltation, causing inconvenience in community use of the affected river water	✓ Set up sediment traps along rivers and/or gabions along banks to filter out eroded sediments ✓ Same measures above for erosion control and slope stabilization	☐# public complaints received by Proponent/ Contractor	Contractor:	
	✓ Oil & grease contamination of waterbodies due to poor equipment M&R & refuelling	□ Provide oil & grease traps in stilling ponds ✓Provide ring canals around fuelling tanks/ motorpool/ maintenance areas ✓Collect used oils in containers	☐ Presence of oil film on water surface; ☐ # public complaints received by Proponent/ Contractor	Contractor:	
	✓ Decreased public access through the construction area	✓ Designate an alternate route for pedestrian and vehicles in coordination with the LGU or provide safe passageway thru the construction site	□# public complaints received by Proponent/ Contractor	Contractor:	
	✓ Increased traffic due to frequent heavy equipment/ vehicle movement	✓ Schedule vehicle movement during lean daytime traffic hours or at night. ✓ Provide traffic aides/flagmen (e.g. thru barangay), traffic signs to help ensure the free and safe flow of traffic ✓ Maintain & Repair temporary alternative route of vehicles & pedestrians.	□ Presence of traffic signs □# of public complaints received by Proponent/ Contractor □ Occurrence of traffic build-up	Contractor:	
	✓Increased community hazards	✓ Provide appropriate warning signs, lighting and barricades,	☐ Presence of signages	Contractor:	

Project Phase / Activities	Possible Environmental Impacts	Mitigating Measures	Monitoring Parameters	Responsib le Agency/ Unit	Cost of Mitigation/ Monitoring
	of vehicular accidents and construction works	whenever practicable Vobserve traffic rules, e.g. vehicle speed Observe proper housekeeping during construction and demobilization to clear site of construction debris Provide on-site medical services and supplies for any emergency, thru institutional and administrative arrangements with the barangay health unit	□# of accidents □ Presence of scattered construction debris		
	✓ Occupational health hazards to workers	✓Require all workers to strictly observe safety standards ✓Put up safety signs along the road construction route ✓Provide potable water & sanitary facilities for construction workers	☐ Presence of signages ☐ Quality of water source ☐ Presence of adequate sanitaty facilities ☐ # of medical complaints or cases	Contractor:	
	✓ Increased micro- economic activity within the area	✓ Coordinate with the LGU on management of traffic & handling of solid waste ✓ Comply with city/town ordinances	☐# businesses ☐Presence of clean commercial area ☐Low traffic	Contractor:	
	Damage to cultural property which may be traversed or encountered during construction	☐ Reroute road, if possible ☐ If not possible to reroute, observe reporting and conservation protocols based on prior coordination with the NHI/NM	□ Presence of clearance □# of public complaints received by Proponent & Contractor	Contractor:	
	✓ Impact to IPs, women & other vulnerable groups who may be affected by the road construction, including those who may be inconvenienced in their use of the river downstream for domestic works.	✓ Addressed by measures to prevent water quality impacts ✓ Prior consultation & coordination to minimize disruption on daily domestic activities & avoid violation of human rights	□# of public complaints received by Proponent & Contractor	Contractor:	
	✓ Over-flooding of the roadway due to excessive accumulation of rainwater and undiverted	✓ Provision of adequate drainage system and proper road grading so that roadway will not be prone to flooding & erosion	☐ Pools of water on the road after rains	Contractor:	

Project Phase / Activities	Possible Environmental Impacts	Mitigating Measures	Monitoring Parameters	Responsib le Agency/ Unit	Cost of Mitigation/ Monitoring
2.2 Monitoring of quality of construction works	waterways Poor M&E or lack of it can result to sub-standard construction or use of sub-standard materials, potentially resulting to structural damages which can unnecessarily expose FMR users to hazards and accidents Good Maintenance result to Quality Assurance for sustainability of FM	✓Regular Project M&E integrates environmental M&E on conformance to original design/specs ✓Allocation of sufficient budget for project M&E ✓Designate, deputize or enter into an agreement with the barangay LGU or local community for transparent M&E of construction works ✓Provision for Contractor's performance bond or withholding final payment until repairs are done before turnover by the Contractor to the LGU/PO/NGO	□ Occurrence of damages during construction □ Visual presence of sub-standard materials □ % completion per schedule and budget	Contractor: LGU: P O/NG O Local Community Rep:	
3.0 Operation	and Maintenance Unsustained FMR operations at optimum capacity due to structural damages	✓Prepare and implement an acceptable O & M Plan ✓Sustained and regular monitoring and maintenance & repair of FMR structure ✓Allocate sufficient budget for M&E and maintenance and repair ✓Designate, deputize or enter into an agreement with the barangay LGU or local community for M&E of the FMR status ✓Provide appropriate load limit sign at FMR approach to lessen/prevent passing of overloaded vehicles	□ No. of accurate reports on O & M status □ No. of back- jobs □ % repaired cracks	□ LGU: □ P O/NG O □ Local Community Rep:	Cost of measures integrated in Project M&E: LGU operations PhP (Note: Signages earlier integrated in Construction Cost)
	✓Obstruction of water flow and aggregation of garbage	✓ Regular removal of debris and other materials clogging the road culverts upstream of the FMR that may obstruct water flow	☐ Occurrence of accumulated garbage upstream of the FMR ☐ Occurrence of damming	☐ LGU ☐ PO/NG O	Debris Collection is LGU cost
	✓ Exposure of FMR users to vehicular hazards	✓ Provide appropriate vehicular safety warning signs at FMR approach	# of accidents	☐ LGU ☐ PO/NG O	Cost of signages was earlier integrated in Construction Cost

	IMPORTANT REMINDER! HAVE YOU DONE THE FOLLOWING BEFORE FINALIZING YOUR PROJECT DESIGN & LOAN DOCUMENTS?		
		YES	NO
a)	Have you re-evaluated the Project Design and integrated the relevant mitigating measures identified in the PD/EMP above ?	/	
b)	Have you actually integrated the corresponding mitigating/monitoring costs into the Final Project Cost?		/

Prepared by:	Endorsed by:
OVETTE C. VIRAY	DIOSDADO G. PALLASIGUE
(Signature over Printed Name)	(Signature over Printed Name)
LGU:	LGU:
PO/NGO:	PO/NGO:
(Date signed)	(Date signed)

Based on the submitted loan application documents:

Final P	PD/EMP Reviewed by:	Reviewed PD/EMP Approved by:
PMO:	(Date signed)	(Signature over Printed Name) PMO: GA: (Date signed)

<u>Distribution of approved copies:</u>

Proponent - original PMO - copy GA- copy