

Republic of the Philippines Department of Agriculture PHILIPPINE RURAL DEVELOPMENT PROJECT

# **Feasibility Study**



**Proponent:** 

Republic of the Philippines Municipality of Sogod Province of Southern Leyte



# D. Social Analysis

# 1.Project Beneficiaries

The project will directly benefit BarangaysSuba, Kanangkaan, San Vicente and San Juan.The fourbarangays have a combined population of 2,151 of which 1,115 (51.8%) are males and 1,036 (48.2%) are females in454 households as of the 2010 census.

Majority of the beneficiaries are farmers engaged in the cultivation of coconuts, abaca, rice, fruits and vegetables and other crops that the barangays are known for. The beneficiaries are eagerly awaiting the implementation of the project considering that the road segment has been in a sorry state of disrepair for a long time.

The residents of said barangays were consulted between July 26-28, 2014 about the subproject. The consultation was attended by barangay officials and residents including women. In the end, all four barangays accepted and endorsed the sub-project. The minutes of the sessions and Barangay Resolutions are found inAnnex 2 of this study.

# 2. Indigenous Cultural Community/Indigenous Peoples (ICC/IP)

The sub-project will not infringe or disturb any indigenous cultural community since there is no cultural minorities living within the area. Likewise, the sub-project will not encroach or traverse in any ancestral domain considering that there is no ancestral domain in the whole of Region 8. This is the reason why the Regional Office of Cultural Minorities based in Tacloban City was closed about ten years ago.

## 3.Site and Right-of-Way Acquisition

The right-of-way has been addressed during InFRES because the LGU-Sogod was able to secure 10 meters of right-of-way and the owners were properly compensated during the InFRES program so there is no need to secure another right-of-way since the proposed sub-project will only have a maximum of 8 meters width inclusive of 1.5 meters shoulder on each side of the road.

# 4. Damage to Standing Crops, Houses and/or Properties

There are three (3) coconut trees in the road shouder in Brgy. Kanangkaan that need to be removed. These trees however are only 3-5 years old and are non-bearing. There is also a 3m. x 5m. waiting shed along the road shouder in Brgy. Suba the portion which is the start of the road sub-project. But it is made of temporary and light materials that can be easily removed. All the safeguards necessary for the removal of both impediments shall be complied with accordingly by using Form 1 & 2 for SES compliance.

## 5. Physical Displacement of Persons

There are no houses that will be affected or relocated during the project so there will be no persons who will be displaced during and after project completion.

## 6. Economic Displacement of Persons

As rehabilitation and concreting project for an existing road section proceeds, no persons will be economically displaced or alienated from their traditional livelihoods. On the contrary, a significant number of local residents will find direct and indirect employment opportunities during project implementation as laborers, workers and vendors among others.

# E. Environmental Assessment

## **1.Natural Habitat**

The proposed project is not within any protected area or wild life sanctuary nor will it entail cutting of trees therefore, the natural environment will not be disturbed or affected in any manner.

## 2.Physical Cultural Resources

There are no historical, cultural, monuments and other physical structures of national cultural value within the project area that will be affected by the rehabilitation and concreting works.

## 3.Terrain, Soil Types and Rainfall

The terrain in the project area is basically rolling and hilly with some mountainous areas. Around 65% of the total land area is within the 15% slope limit which ranges from flat to undulating. The remaining 35% are steep slopes and mountain areas.

There are six types of soils within the sub-project area, namely Sandy Loam, Hydrosol, Maasin Clay, Guimbalan Clay, Undifferentiated Soil Group and Umingan Clay Loam.

The area has no pronounced wet and dry season. Rainfall is almost evenly distributed throughout the year with an average rainfall of 167.413 mm with maximum rainfall usually recorded in the months of November to February. Minimum rainfall (100mm/month) usually occurs in the months of April to May and August to September. There is no single dry month in these areas. The temperature cool months are October to December each year.

## 4.Hazard/Risk Assessment

With rains evenly distributed throughout the year, the road surface areas and road shoulders are always under threat of rain water and flooding. These will be mitigated by introducing road cambers leading the water runoff immediately outside of the roadway into the intercepting canals and drainage outlets and own to the receiving rivers and streams. Likewise, trees shall be planted at the edges of the road shoulders to mitigate the flow of rain water to the road surface and shoulders.

## 5.Status of Environmental Clearances

The LGU of Sogod has pending applications for the Environmental Clearance Certificate (ECC), Certificate of Non- Compliance (CNC), Quarry Permit (QP) and other government regulatory clearances required for this project.

It is expected that all these clearances will be obtained by the LGU before actual project implementation.

#### **6.Social and Environmental Impacts**

Name of Project	:	Rehabilitation/Concreting of Suba-Kanangkaan-San Vicente-San Juan Farm to Market Road.	
Location	:	Brgys.Suba, Kanangkaan, San Vicente, and San Juan Municipality of Sogod, Province of Southern Leyte	
Implementing LGU	:	LGU of Sogod, Southern Leyte	
No. of Beneficiaries	:	2,151 Direct Beneficiaries, 454 Households	
Type of Work	:	Rehabilitation and Concreting	
Estimated Project Cost:		Php 30,573,932.90	

#### a.Site and Design Consideration

The following are the principal considerations in the formulation and conduct of the Detailed Engineering Designs (DED) for the rehabilitation and concreting project:

- i. The road project does not traverse or encroach into declared protected areas and wild life sanctuaries nor shall it affect any settlements or communities populated with indigenous people;
- ii. The project shall not displace, destroy or render inoperable/inaccessible any monument or physical structure of known historical and cultural values, and;
- iii. The project does not destroy any house, standing crops or displace any person from his home and main sources of livelihood and income.

#### b. Impacts During Construction

#### i. Temporary Erosion and Sediment Control

Erosion and sediment control in construction areas will prevent sediment discharge to nearby streams and rivers. Areas cleared of vegetation for construction and roadway development should be minimized and slopes should be stabilized. Overland drainage should be controlled to prevent channelling and sediment transport by diverting flows from areas where soils are exposed, and/or by providing filter barriers or settling basins to remove sediment before the runoff is discharged to surface waters.

#### ii. Construction Noise Mitigation

There are houses and establishments along and nearby the construction site especially along the built-up areas. The construction involves the operation of heavy equipment and will undoubtedly generate loud noises. As a mitigating measure, work activities should be avoided during quiet periods of the day.

#### iii. Proper Handling of Construction Wastes

The sub-project will generate surplus common excavation materials and debris. Disposal sites have been identified to haul these surpluses outside the limits of the road right of way. This will minimize the amount of site litters and will prevent the indiscriminate dumping of surpluses along the roadsides. Assurances is made by the LGU that these wastes will be collected and properly disposed of in accordance with government regulations.

## iv. Public and Worker's Safety

Safety of workers and the public must be given priority. Standard construction safety protocols must be observed at all times, such as posting of road signs.

## c. Environmental / Social Issues and Mitigating Measures

Table 16. Project's Potential Impact, Assessment and Mitigating Measures

lssues (Potential Impact)	Assessment	Mitigation Measure	Instrument of Implemen- tation (POW, Contract, IDP, or O&M Plan	Sche- dule	Respon- sible
1. Temporary increase in sedimentation during construction	<ul> <li>[x] Topography of the road alignment necessitate massive earthmoving and cutting of clayey or loose topsoil</li> <li>[] Cut materials will consist mainly of hard rocks and are unlikely to generate significant sediments</li> </ul>	<ul> <li>[x]Earthmoving/cut ting of slopes to be done during dry days at Station 4 + 240 to Station 4 + 640</li> <li>[] No measures required</li> </ul>	Contract	During Cons- truction	Con- tractor
2. Potential contamination of surface and ground water with oil/grease	<ul> <li>[] Waste oil and grease from equipment could contaminate surface water</li> <li>[x] There will be no significant amount of waste oil and grease</li> </ul>	[x] Proper handling and disposal of waste oil and grease	Contract	During Cons- truction	Con- tractor
3. Potential contamination with human waste	<ul> <li>[] Construction workers would be temporarily housed in a base camp</li> <li>[x] Workers would be mostly locals and are expected to go home to their respective houses after work</li> </ul>	<ul> <li>[] Set up adequate latrine/toilet facility at the base camp</li> <li>[x] No mitigating measure needed</li> </ul>	- N/A	- N/A	- N/A
4. Potential disruption of traffic flow	<ul> <li>[x] The access roads and/or segments to be rehabilitated is vital to daily activities of the residents and farmers and need to be kept open to traffic during construction</li> <li>[] The construction will not affect daily movement of residents and farmers</li> </ul>	<ul> <li>[x] Keep the road open to traffic flow and mini- mize disruptions along the access road and/or construction area; Provide adequate warning signs and traffic personnel when necessary;</li> <li>[] No measures needed</li> </ul>	Contract	During Cons- truction	Cont- ractor

lssues (Potential Impact)	Assessment	Mitigation Measure	Instrument of Implemen- tation (POW, Contract, IDP, or O&M Plan	Sche- dule	Respon- sible
5. Potential dust/mud nuisance during construction	<ul> <li>[x]Roads could become powdery during dry days and muddy during rainy days of the construction</li> <li>[] Access roads and/or the construction/ rehabilitation passes through a populated area</li> <li>[] Access road and/or construction/ rehabilitation does not pass through any populated area</li> </ul>	<ul> <li>[x] Undertake sprinkling of roads (including access roads) during dry days, and filling up of potholes during rainy days, especially in residential areas</li> <li>[] Set up speed limits for vehicles, especially within residential areas</li> <li>[] No measures needed</li> </ul>	Contract	During Cons- truction	Cont- ractor
6. Landslide erosion of exposed road sides resulting in sedimenta-tion of waterways	<ul> <li>[X] The road will traverse a mountainous area necessitating deep cuts in mountain-sides particularly between Station 4 + 240 to Station 4 + 640.</li> <li>[] The exposed slopes will likely consist of highly erodible loose materials</li> <li>[] The cut slopes will be hard materials that would resist erosion</li> <li>[] The road passes through a relatively benign terrain, cuts will be minimal</li> <li>[] The rehabilitation work does not involve additional road cuts</li> </ul>	<ul> <li>[] Include slope protection works at the following stations:</li> <li>[] Bioengineering with geomat and cover crop</li> <li>[] Fast growing shrub</li> <li>[] Riprap</li> <li>[] Gabions</li> <li>[x] Terracing at Station 4 + 240 to Station 4 + 640</li> <li>[] Concrete protection wall</li> </ul>	Contract	During Cons- truction	Cont- ractor
7. Inadequate drainage resulting in flooding or ponding	[x] The road will block runoff, resulting in flooding on one side of the road during rainy days [] Drainage issues unlikely	[] Installation of cross drain between stations [x] Lined ditch at Station 4 + 240 to Station 4 + 640	Contract	During Cons- truction	Cont- ractor
8. Potential increase in use of pesticides due to intensification of cash crop production	<ul><li>[x] There is an going IPM Program of DA in the service area</li><li>[] Farmers in the service area have not been trained on IPM</li></ul>	<ul> <li>[x] DA to continue to support IPM Program</li> <li>[] LGU to coordinate with DA on IPM Training</li> </ul>	-	Conti- nuing	DA/ MAO

lssues (Potential Impact)	Assessment	Mitigation Measure	Instrument of Implemen- tation (POW, Contract, IDP, or O&M Plan	Sche- dule	Respon- sible
9. Potential acceleration of denudation of upland/hilly areas due to intensification of crop production	<ul> <li>[x] The proposed road will connect to the market an upland/hilly area where farmers are currently practi-cing erosive farming techniques. The road could help accelerate the denudation of upland/hillsides rendering them unproductive un a few years.</li> <li>[] The road connects only lowland farms to the market</li> </ul>	<ul> <li>[X] DA to coordinate with LGU for the introduction of sustainable upland farming systems in the area.</li> <li>[] No measure required</li> </ul>	DA-LGU Memo of Agreement	Cont- inuing	DA & LGU- Sogod
10. Potential increase in encroach- ments of human activities into the nearby public forests	<ul> <li>[x] The proposed road will improve human access to the nearby forest, resulting in increasedin slash and burn cultivation, illegal logging and poaching.</li> <li>[] The proposed road does not improve access to a public forest</li> </ul>	<ul> <li>[x] Coordinate</li> <li>with DENR for</li> <li>the enactment</li> <li>of ordinance</li> <li>deputizing the</li> <li>local</li> <li>community to</li> <li>enforce forestry</li> <li>laws</li> <li>[] No measure</li> <li>required</li> </ul>	DENR-LGU Memo of Agreement	During Project imple- menta- tion	DENR & LGU- Sogod
11. Local Employment	<ul> <li>[x] Construction will provide local employment opportunities</li> <li>[] Construction does not provide local employment opportunities</li> </ul>	<ul> <li>[x] Hiring priority shall be given to qualified local residents; Implement RI Manual on local hiring</li> <li>[] No measures required</li> </ul>	Contract	During Project imple- menta- tion	Contrac tor
12. Conversion of Land- use/natural habitat due to quarry	<ul> <li>[] The proposed quarry site is within a private land and need to convert existing land-use</li> <li>[x] Quarry site is existing and proven as a good source of quarry materials</li> </ul>	[x] Quarry materials will be procured from existing quarry sites	Certification	Before Project imple- menta- tion	LGU- Sogod
13. Potential damage to existing road due to hauling of quarry materials	<ul> <li>[x] Source of quarry materials (Items 200 &amp; 201)is 1 km.away.</li> <li>Transportation of quarry materials from source to FMR will cause damage to existing FMR</li> </ul>	[x] Regular maintenance and repair of existing road	Local Road Mainte- nance Plan	During & after Cons- truction	LGU- Sogod

# 7. Responsible Unit

The Local Government Unit of Sogod, Southern Leyte, being the implementing organization, is primarily responsible to ensure that all mitigating measures must be properly implemented and monitored during project execution.